

# BAGGAGE HANDLING, FRANKFURT MAIN AIRPORT



**New Construction of Tunnel for Baggage Handling System, Frankfurt Main Airport, Germany**

**Project period**  
2008 - 2011

**Construction cost**  
63 M € approx.

**Services provided**  
Project planning of engineering structures, structural engineering  
Technical equipment: preliminary, design and approval planning, tendering

**Technical details**  
Tunnel in shield driving method 1 586 m with inside diameter = 7.54 m  
Tunnel in cut-and-cover construction method 172 m  
Underground extension of transit luggage hall (gross built volume = 11 500 m<sup>3</sup>)

